
Field Test Project for RES Penetration in Niijima Island Grid

October 17th, 2018 IRED 2018



Jun Johkaji Vice President TEPCO Research Institute (TRI) Tokyo Electric Power Company Holdings



©Tokyo Electric Power Company Holdings, Inc. All Rights Reserved.

1.R&D Project on Grid Integration of Variable Renewable Energy ¹

Mitigation Technologies on Output Fluctuations of Renewable Energy Generations in Power Grid \sim Improving technologies on prediction, control, and operation for addressing the output fluctuations \sim

Development Items:

Item (I): Wind power output forecast and enhanced control technology

Item (II): Power system simulation with the forecast technology

Item (III): Enhanced renewable energy connection with power grid

Purpose: By focusing on variable output (ramp) of wind power generation which affects power system operation, proper forecast and appropriate control technologies will be developed, and appropriate operation method with these technologies will be established. In addition, a remote output control system, which is obligated to be installed, will be developed and established for stable and maximum use of renewable energy.

	R&D Items	2014 FY	2015 FY	2016 FY	2017 FY	2018 FY		
I	Development of prediction technologies of ramp		Development of prediction technologies			Evaluation, improvement		
	Development of control technologies of energy storage facilities	Development of control technologies, installation of equipment			Field test, improvement			
П	Development of demand and supply simulation systems	Establishment of prototype model			System creation, evaluation			
	Demonstration test of power grid system	Specification study, installation of equipment			Field test, evaluation			
Ш	Enhanced renewable energy connection with power grid (wind power)	Niijima	Specifica develop	ation study, ment	Field t evalua	'		
	Enhanced renewable energy connection with power grid (solar power)	Project		Study, developmer	Field t evalua	' \		


Schedule of this project

2. Outline of Niijima Project


To demonstrate massive introduction of renewable energy sources (RES), field tests in the grid in an island were performed. Main study items are as follows:

- 'Output power prediction' and 'Output power control' of RES

- 'Supply-Demand Operation' in coordination with RES, energy storage, and existing power generations.




3. Overview of Niijima Island




Total demand 1,900kW~4,400kW

TEPCO

4. Layout of Facilities



5. Project Organization



6. Schedule

Investigation, pre-study and construction of facilities (2014 – 2017)
 Combination test of each facility and function (2017 – 2018)

	-			Fis	scal year
Action Items	2014	2015	2016	2017	2018
 1. Investigation (1) Amount of insolation and wind condition (2) Characteristics of demand and power supply 					
 2. Pre-study (1) Development of simulation model (2) Pre-study by simulator system 					
 3. Facility construction (1) Design of test facilities, control system (2) Construction of facilities, control system 					
 4. Field test (1)Testing and adjustment of test facilities (2) Evaluation 					



7. Overview of Facilities(1)

(1) Wind Power Generation

- < Connection to grid: Nov. 2016 >
 - WT: 300kW * 2
 - Battery: Lithium ion battery (500kWh)
 - Inverter: 500kW


(2) Photovoltaic Power Generation

- < Connection to grid: Dec. 2015 >
- PV: 318kW (255W Polycrystalline module, 1,440 panels)
- Inverter: 315kW

(3) Large-scale Storage Battery

- < Connection to grid: Oct. 2015 >
- Battery: Lithium ion battery (500kWh * 2)
- Converter: 1,000kW * 2







(2) Photovoltaic Power Generation





8. Overview of Facilities(2)

(4) Small-type PV and Storage Battery

(9 sites; elementary school, junior high school, and clinic and so on)

- PV: 5kW 12kW
- Lithium ion battery: 12kWh (Capacity)
- Converter: 10kW

(5) Heat Pump (Mamashita hot springs)

- Heat capability: 56kW
- Power consumption: 16kW

(6) Cooling Facility (Fish port)

- Cooling capability: 78kW
- Power consumption: 35kW












9. Output Prediction of RES

Weather Observation Equipment






10. Distributed Coordinated Control System (1)

Demonstrating the feasibility of optimal integrated grid

* Output prediction, control, and curtailment of wind and solar power generation
* Cooperative control with existing power source and storage battery



©Tokyo Electric Power Company Holdings, Inc. All Rights Reserved.

11. Distributed Coordinated Control System (2)

Outline of Control


		Purpose	Control	Control Object
Output fluctuation	bud	Compensation of prediction error of RES generation	-Battery Control -Curtailment Control of RES -Demand-side Control	-Large-scale Battery -Wind and PV Generation -Heat Source System
	term	Demand-Shift Control	-Battery Control -Demand-side Control	-Large-scale Battery -Heat Source System
	Short term	Mitigation of RES Output Variation at RES Site (ΔP)	-Battery Control	-Large-scale Battery in WT site
		Mitigation of Frequency Variations (ΔF)	-Battery Control	-Large-scale Battery
		Load Frequency Control (LFC)	-Battery Control -Diesel engine Control	-Large-scale Battery -Diesel engine Control




12. Distributed Coordinated Control System (3)

Frequency Control

- Primary Freq. Control: On-site control avoiding time-delay of controllers
- Secondary Freq. Control: Remote control based on economical control perspectives



13. Overview of Field Test



14. Summary of the Study and the Next Step

Summary of the Study

To demonstrate massive introduction of renewable energy, the following study items were performed in the grid of an island.

- ✓ Output power prediction of RES
- ✓ Output power control of RES
- Supply-Demand Operation which can coordinate with existing power generations, RES, energy storage

The Next step

RES penetration leads to reduction of conventional synchronous generators, which causes decrease of inertial force of the grid, and results in deterioration of power system stability.

Technology to estimate inertial force of the grid and maintain it against RES penetration will be required.



Danke für Ihre Aufmerksamkeit !



Moai statue of Niijima Island